

SHEET NOTES \bigcirc

PROVIDE DEDICATED CIRCUIT FOR TURNSTILES. EACH TURNSTILE ARM REQUIRES A CONNECTION. COORDINATE EXACT REQUIREMENTS WITH

MOUNT RECEPTACLE IN MILLWORK. COORDINATE EXACT REQUIREMENTS WITH

- MILLWORK DESIGNER PRIOR TO ROUGH-IN.
- 3. CIRCUIT RECEPTACLES WITHIN BOUNDARY
- 4. PROVIDE DEDICATED 120V, 20A CIRCUIT TO

- 6. PROVIDE 120V CONNECTION TO
- MOTORIZED SHADE CONTROL SWITCH. COORDINATE EXACT LOCATION WITH ARCHITECT PRIOR TO INSTALLATION. SHADE CONTROLS TO BE INCORPORATE INTO THE LIGHTING CONTROL SYSTEM.
- 8. PROVIDE RECEPTACLE FOR CORD CONNECTED ELEVATOR SUMP PUMP.
- 9. PROVIDE RECEPTACLE FOR ELEVATOR

8000 South Federal Way Boise ID 83707

811 SW 6TH AVE SUITE 300 PORTLAND, OR 97204



TEL 971.277.2370

pae-engineers.com

Lumald.com

- SCHEDULES FOR EQUIPMENT CONNECTION
- B. PROVIDE #10 CONDUCTORS FOR RECEPTACLE CIRCUITS EXCEEDING TOTAL LENGTH OF 100 FEET BETWEEN DEVICE AND
- C. PROVIDE 3/4-INCH CONDUIT AND #12 AWG CONDUCTORS FOR 20-AMP BRANCH CIRCUITS UNLESS NOTED OTHERWISE.
- D. COORDINATE ELECTRICAL INSTALLATION WITH MECHANICAL AND PLUMBING PLANS FOR EQUIPMENT LOCATIONS PRIOR TO
- SIGHT OF AND ADJACENT TO EQUIPMENT SERVED UNLES OTHERWISE NOTED.
- LOCKABLE WEATHERPROOF WHILE-IN-USE
- G. REFER TO DEVICE SCHEDULE ON SHEET **E0.207** FOR MORE INFORMATION ON FLOOR DEVICES.

11/18/2022 INTERIORS 50% DESIGN DEVELOPMENT 12/16/2022 INTERIORS 100% DESIGN DEVELOPMENT 02/03/2023 CONSOLIDATED PROGRESS SET 05/02/2023 PROGRESS SET 12/22/2023 CD PROGRESS SET FOR PERMIT AND 02/22/2024 CD - MEP BID SET 03/29/2024 Issue for Permit 1 10/11/2024 ISSSUE FOR CONSTRUCTION 2 12/06/2024 BULLETIN #1

Seal / Signature

MICRON BUILDING B42

22-1717

ELECTRICAL PLAN LEVEL 1 - SECTOR B

1/8" = 1'-0"

E1.301B