


1/26/2024, 11:30:48 AM Autodesk Docs Micron-HQ Campus 2022PAE-S05-E1.MAN-000001.dwg



1 POWER PLAN LEVEL 5 - SECTOR B  
1/8" = 1'-0"

SHEET NOTES

1. PROVIDE FURNITURE FEED POWER WHIPS. COORDINATE EXACT REQUIREMENTS WITH MANUFACTURER PRIOR TO ROUGH-IN. COORDINATE WITH TECHNOLOGY AND AV DRAWINGS FOR ADDITIONAL REQUIREMENTS.
2. MOUNT RECEPTACLE IN MILLWORK. COORDINATE EXACT REQUIREMENTS WITH MILLWORK DESIGNER PRIOR TO ROUGH-IN.
3. CIRCUIT RECEPTACLES WITHIN BOUNDARY TO NL5814B, UNLESS OTHERWISE NOTED.
4. CIRCUIT RECEPTACLES WITHIN BOUNDARY TO NL5824B, UNLESS OTHERWISE NOTED.
5. PROVIDE DEDICATED 120V, 20A CIRCUIT TO HAND DRYER.
6. PROVIDE 120V CONNECTION TO AUTOMATED FAUCET.
7. PROVIDE RECEPTACLE FOR DIGITAL SIGNAGE MOUNTED IN PACS28 BOX (PROVIDED BY OTHERS). COORDINATE EXACT REQUIREMENTS WITH AV CONTRACTOR PRIOR TO ROUGH-IN.

GENERAL NOTES

- A. REFER TO EQUIPMENT CONNECTION SCHEDULES FOR EQUIPMENT CONNECTION REQUIREMENTS.
- B. PROVIDE #10 CONDUCTORS FOR RECEPTACLE CIRCUITS EXCEEDING TOTAL LENGTH OF 100 FEET BETWEEN DEVICE AND PANEL.
- C. PROVIDE 3/4-INCH CONDUIT AND #12 AWG CONDUCTORS FOR 20-AMP BRANCH CIRCUITS UNLESS NOTED OTHERWISE.
- D. COORDINATE ELECTRICAL INSTALLATION WITH MECHANICAL AND PLUMBING PLANS FOR EQUIPMENT LOCATIONS PRIOR TO ROUGH-IN.
- E. LOCATE STARTERS/DISCONNECTS WITHIN SIGHT OF AND ADJACENT TO EQUIPMENT SERVED UNLESS OTHERWISE NOTED.
- F. PROVIDE EXTERIOR DEVICES WITH LOCKABLE WEATHERPROOF WHILE-IN-USE COVERS.
- G. REFER TO DEVICE SCHEDULE ON SHEET E1.305B FOR MORE INFORMATION ON FLOOR DEVICES.



8000 South Federal Way  
Boise ID 83707



811 SW 6TH AVE  
SUITE 300  
PORTLAND, OR 97204  
TEL 971.277.2370



pae-engineers.com



Lumald.com

Date	Description
11/18/2022	INTERIORS 50% DESIGN DEVELOPMENT
12/16/2022	INTERIORS 100% DESIGN DEVELOPMENT
02/03/2023	CONSOLIDATED PROGRESS SET
05/02/2023	PROGRESS SET
12/22/2023	CD PROGRESS SET FOR PERMIT AND PRICING
02/22/2024	CD - MEP BID SET
03/28/2024	Issue for Permit
1 10/11/2024	ISSUE FOR CONSTRUCTION
2 12/06/2024	BULLETIN #1

Seal / Signature

Project Name

MICRON BUILDING B42

Project Number

22-1717

Description


ELECTRICAL PLAN LEVEL 5  
- SECTOR B

Scale

1/8" = 1'-0"

E1.305B

KEY



City of Boise Stamps