

SHEET NOTES \bigcirc

1. PROVIDE FURNITURE FEED POWER WHIPS. COORDINATE EXACT REQUIREMENTS WITH MANUFACTURER PRIOR TO ROUGH-IN. COORDINATE WITH TECHNOLOGY AND A/V DRAWINGS FOR ADDITIONAL REQUIREMENTS.

PROVIDE DEDICATED 120V, 20A CIRCUIT TO HAND DRYER.

3. PROVIDE 120V CONNECTION TO

4. MOUNT RECEPTACLE IN MILLWORK. COORDINATE EXACT REQUIREMENTS WITH MILLWORK DESIGNER PRIOR TO

AUTOMATED FAUCET.

PROVIDE 120V CONNECTION TO MOTORIZED SHADES.

ROUGH-IN.

6. MOTORIZED SHADE CONTROL SWITCH. COORDINATE EXACT LOCATION WITH ARCHITECT PRIOR TO INSTALLATION. SHADE CONTROLS TO BE INCORPORATED INTO THE LIGHTING CONTROL SYSTEM.



Gensler

811 SW 6TH AVE SUITE 300 PORTLAND, OR 97204 TEL 971.277.2370



pae-engineers.com

Lumald.com

GENERAL NOTES

- A. REFER TO EQUIPMENT CONNECTION SCHEDULES FOR EQUIPMENT CONNECTION REQUIREMENTS.
- B. PROVIDE #10 CONDUCTORS FOR RECEPTACLE CIRCUITS EXCEEDING TOTAL LENGTH OF 100 FEET BETWEEN DEVICE AND
- C. PROVIDE 3/4-INCH CONDUIT AND #12 AWG CONDUCTORS FOR 20-AMP BRANCH CIRCUITS UNLESS NOTED OTHERWISE.
- D. COORDINATE ELECTRICAL INSTALLATION WITH MECHANICAL AND PLUMBING PLANS FOR EQUIPMENT LOCATIONS PRIOR TO ROUGH-IN.
- E. LOCATE STARTERS/DISCONNECTS WITHIN SIGHT OF AND ADJACENT TO EQUIPMENT SERVED UNLESS OTHERWISE NOTED.
- F. PROVIDE EXTERIOR DEVICES WITH LOCKABLE WEATHERPROOF WHILE-IN-USE
- G. CIRCUIT RECEPTACLES TO PANEL NL7B24B, UNLESS OTHERWISE NOTED.
- H. REFER TO DEVICE SCHEDULE ON SHEET **E0.207** FOR MORE INFORMATION ON FLOOR DEVICES.

11/18/2022 INTERIORS 50% DESIGN DEVELOPMENT 12/16/2022 INTERIORS 100% DESIGN DEVELOPMENT 02/03/2023 CONSOLIDATED PROGRESS SET 05/02/2023 PROGRESS SET 12/22/2023 CD PROGRESS SET FOR PERMIT AND 02/22/2024 CD - MEP BID SET 03/29/2024 Issue for Permit 1 10/11/2024 ISSSUE FOR CONSTRUCTION 2 12/06/2024 BULLETIN #1

Seal / Signature

MICRON BUILDING B42

22-1717

ELECTRICAL PLAN LEVEL 7 - SECTOR C

E1.307C