

SHEET NOTES \bigcirc

PROVIDE FURNITURE FEED POWER WHIPS. COORDINATE EXACT REQUIREMENTS WITH MANUFACTURER PRIOR TO ROUGH-IN. COORDINATE WITH TECHNOLOGY AND A/V DRAWINGS FOR ADDITIONAL REQUIREMENTS.

- PROVIDE DEDICATED 120V, 20A CIRCUIT TO HAND DRYER.
- AUTOMATED FAUCET. 4. CIRCUIT RECEPTACLES WITHIN BOUNDARY TO NL7B21A, UNLESS

3. PROVIDE 120V CONNECTION TO

- OTHERWISE NOTED. 5. CIRCUIT RECEPTACLES WITHIN
- BOUNDARY TO NL7B11A, UNLESS OTHERWISE NOTED. 6. CIRCUIT RECEPTACLES WITHIN

BOUNDARY TO NL7B31A, UNLESS

PROVIDE RECEPTACLE FOR DIGITAL SIGNAGE MOUNTED IN PAC526 BOX (PROVIDED BY OTHERS). COORDINATE EXACT REQUIREMENTS WITH AV CONTRACTOR PRIOR TO ROUGH-IN.

OTHERWISE NOTED.

Boise ID 83707

Gensler

811 SW 6TH AVE TEL 971.277.2370 SUITE 300 PORTLAND, OR 97204

pae-engineers.com

Lumald.com





GENERAL NOTES

- A. REFER TO EQUIPMENT CONNECTION SCHEDULES FOR EQUIPMENT CONNECTION REQUIREMENTS.
- PROVIDE #10 CONDUCTORS FOR RECEPTACLE CIRCUITS EXCEEDING TOTAL LENGTH OF 100 FEET BETWEEN DEVICE AND
- PROVIDE 3/4-INCH CONDUIT AND #12 AWG CONDUCTORS FOR 20-AMP BRANCH CIRCUITS UNLESS NOTED OTHERWISE.
- COORDINATE ELECTRICAL INSTALLATION WITH MECHANICAL AND PLUMBING PLANS FOR EQUIPMENT LOCATIONS PRIOR TO
- E. LOCATE STARTERS/DISCONNECTS WITHIN SIGHT OF AND ADJACENT TO EQUIPMENT SERVED UNLESS OTHERWISE NOTED.
- F. PROVIDE EXTERIOR DEVICES WITH LOCKABLE WEATHERPROOF WHILE-IN-USE
- G. REFER TO DEVICE SCHEDULE ON SHEET E0.207 FOR MORE INFORMATION ON FLOOR DEVICES.

11/18/2022 INTERIORS 50% DESIGN DEVELOPMENT 12/16/2022 INTERIORS 100% DESIGN DEVELOPMENT 02/03/2023 CONSOLIDATED PROGRESS SET 05/02/2023 PROGRESS SET 12/22/2023 CD PROGRESS SET FOR PERMIT AND PRICING 02/22/2024 CD - MEP BID SET 03/29/2024 Issue for Permit 1 10/11/2024 ISSSUE FOR CONSTRUCTION 2 | 12/06/2024 | BULLETIN #1

- SECTOR A