



DEMAND FACTOR TABLE	
THE % SHOWN IN EACH PANEL SCHEDULE IS THE RESULTING RATIO OF DEMAND TO CONNECTED LOAD AFTER APPLYING THE CALCULATION METHODS DESCRIBED BELOW	
DEMAND FACTOR	CALCULATION METHOD PER IDAHO ELECTRICAL CODE
NON- CONTINUOUS	100%
CONTINUOUS	125% PER NEC 215.2(A)(1)(a)
MOTOR	LARGEST MOTOR LOAD ON THE PANEL AT 125%, PLUS 100% OF REMAINING MOTOR LOAD(S) PER NEC 430.24
RECEPTACLE	100% OF THE FIRST 10 KVA AND THE REMAINDER AT 50% PER NEC 220.44
KITCHEN	CALCULATED ACCORDING TO QUANTITY OF KITCHEN EQUIPMENT CONNECTIONS PER NEC TABLE 220.56.
ELEVATOR	BASED ON QUANTITY OF ELEVATORS CIRCUITED TO THE PANEL PER NEC TABLE 620.14
DRYERS	IN DWELLING UNIT(S): BASED ON QUANTITY OF DRYERS CIRCUITED AT EACH BUS PER NEC 220.54
IMAGING	PER NEC SECTION 517.73(A)(2): FOR FEEDERS WITH TWO OR MORE X-RAY UNITS, 50% OF MOMENTARY DEMAND RATING OF THE LARGEST UNIT, PLUS 25% MOMENTARY DEMAND RATING OF THE NEXT LARGEST UNIT, PLUS 10% OF MOMENTARY DEMAND RATINGS OF ALL REMAINING UNITS.

3 LOAD CLASSIFICATION TABLE NONE





8000 South Federal Way Boise ID 83707

Gensler

811 SW 6TH AVE SUITE 300 PORTLAND, OR 97204



TEL 971.277.2370

pae-engineers.com

Lumald.com

11/18/2022 INTERIORS 50% DESIGN DEVELOPMENT
12/16/2022 INTERIORS 100% DESIGN DEVELOPMENT
02/03/2023 CONSOLIDATED PROGRESS SET
05/02/2023 PROGRESS SET
12/22/2023 CD PROGRESS SET FOR PERMIT AND PRICING
02/22/2024 CD - MEP BID SET
03/29/2024 Issue for Permit
1 10/11/2024 ISSSUE FOR CONSTRUCTION

Project Name

MICRON BUILDING B42

Project Number

22-1717

DETAILS - ELECTRICAL

Scale
NOT TO SCALE

E5.001

City of Boise Stamps